

PLEXEON LOGISTICS INC Data Center Overview

Facility 1:

- Area:** 40,000 Square Feet
- Fiber Route:** Diverse Fiber Optic facility entrances
- Power:** 5000 Amp 480v AC Main Paralleling switchgear.
Utility Status.
Back up power provided by two - 1,000 kW diesel generators with a 48-hour fuel supply.
- Fire Suppression:** Ready conversion from wet system to a dry pipe system.
Pre-action system linked to smoke and heat detectors.
- Grounding:** A PVC conduit is provided from the main facility Ground.
- HVAC:** Conditioned space with temperatures maintained between 65 and 75 degrees F and relative humidity between 40 and 60%.
- General:** All space conditioning is monitored through a building automatic controls system.
- Internet Bandwidth:** 2 Gbps capacity - (2 separate bandwidth providers)

Facility 2:

- Area:** 10,000 Square Feet
- Connection:** 1 Gbps private connection to Facility 1
- General:** All space conditioning is monitored through building central control.

